Estimate of Materials and Cost of Construction



Project Name: Address: Date:

Summary	Amount			
Subtotal	\$ 292,950			
Profit/Overhead	\$ 73,238			
Total	\$ 366,188			

ITEM#	DESCRIPTION	QTY.	FT	QTY. W/	UNIT	UNIT	ITEM	TRADE
				FT		COST	COST	COST
	FIRE ALARM							\$ 292,950
1	17"x30"x36"D Fire alarm underground	6	0%	6	ea	\$ 350.00	\$ 2,100	
	pullbox							
2	Access panel	103	0%	103	ea	\$ 600.00	\$ 61,800	
3	Addressable control relay module	35	0%	35	ea	\$ 400.00	\$ 14,000	
	mounted on 4s box							
4	Addressable control relay	35	0%	35	ea	\$ 350.00	\$ 12,250	
5	Addressable manual pull station	3	0%	3	ea	\$ 550.00	\$ 1,650	
	mounted in 4s deep							
6	Addressable monitor module mounted on standard	29	0%	29	ea	\$ 325.00	\$ 9,425	
	Addressable dual monitor module	2	0%	2	ea	\$ 550.00	\$ 1,100	
7	mounted on 4s box	2	U%0	2	ea	\$ 330.00	\$ 1,100	
7	Addressable photo smoke detector,	183	0%	183	ea	\$ 250.00	\$ 45,750	
/	ceiling mounted	103	070	163	Ca	\$ 230.00	\$ 45,750	
8	Addressable thermal heat detector,	101	0%	101	ea	\$ 200.00	\$ 20,200	
	mounted in attic							
9	Fire alarm document cabinet	3	0%	3	ea	\$ 450.00	\$ 1,350	
10	Fire alarm nac/expander panel	1	0%	1	ea	\$ 400.00	\$ 400	
11	Fire alarm remote annunciator panel	2	0%	2	ea	\$ 1,200.00	\$ 2,400	
12	Fire alarm strobe mounted flush on 4s deep box	39	0%	39	ea	\$ 450.00	\$ 17,550	
13	Fire alarm system voice evacuation remote	2	0%	2	ea	\$ 450.00	\$ 900	
14	Fire alarm terminal cabinet	14	0%	14	ea	\$ 450.00	\$ 6,300	
15	Fire alarm access door	17	0%	17	ea	\$ 500.00	\$ 8,500	
16	Siemens fire alarm control voice evacuation panel	2	0%	2	ea	\$ 350.00	\$ 700	
17	Siemens fire alarm transponder panel	5	0%	5	ea	\$ 300.00	\$ 1,500	
18	All exterior speakers to be tapped with weatherproof	70	0%	70	ea	\$ 450.00	\$ 31,500	
19	All interior speakers to be tapped	68	0%	68	ea	\$ 150.00	\$ 10,200	
20	Fire alarm sprinkler tampper	4	0%	4	ea	\$ 300.00	\$ 1,200	
21	Fire alarm expender panel	5	0%	5	ea	\$ 1,200.00	\$ 6,000	
22	Seimens remote power supply for carbone monoxide dectector	1	0%	1	ea	\$ 300.00	\$ 300	
23	Penetration of walls	187	0%	187	loc	\$ 125.00	\$ 23,375	
24	Trenching and backfilling	1	0%	1	ls	\$ 12,500.00	\$ 12,500	
SUB TOTAL		- 1	0.0	-				\$ 292,950
INSURANCE						3%	\$ 8,789	\$ 8,789
OVERHEAD ANI	D PROFIT					22%	\$ 64,449	\$ 64,449
TOTAL BASE BI							\$ 366,188	\$ 366,188

General Notes: The prices used while preparing the estimate were taken from RSMeans online i.e. the standard pricing & the company is not

- 1 The drawings are scaled as per the mentioned scales on the
- 2 The prices used are standard prices, unless otherwise noted.

F.C = Waste or diff.sf = square feet

Legend

lf = linear feet

ea = eachcy = cubic yard

Exclusions 1 Union Wages

sy = square yard loc = location ls = lump sum